

3-8-77 Footage location changed to: 100' FSH + 10  
6-17-77 - Shut-in Gas Storage

FILE NOTATIONS

Entered in NID File

Entered On S R Sheet

Location Map Pinned

Card Indexed

I W R for State or Fee Land

Checked by Chief

Copy NID to Field Office

Approval Letter

Disapproval Letter

COMPLETION DATA:

Date Well Completed

OW..... WW..... TA.....

GW..... OS..... PA.....

Location Inspected

Bond released

State of Fee Land

LOGS FILED

Driller's Log

Electric Logs (No. )

E..... I..... E-I..... GR..... GR-N..... Micro.....

Lat..... Mi-L..... Sonic..... Others.....

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

## APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input type="checkbox"/>		D. LEASE DESIGNATION AND SERIAL NO. SL - 045051 b	
b. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		E. IF INDIAN, ALLOTTED OR TRIBE NAME -	
2. NAME OF OPERATOR Mountain Fuel Resources, Inc.		7. UNIT AGREEMENT NAME Clay Basin Gas Storage Agreement	
3. ADDRESS OF OPERATOR P. O. Box 1129, Rock Springs, Wyoming 82901		8. FARM OR LEASE NAME Clay Basin Unit	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.) At surface 950' FSL 1153' FWL SW SW At proposed prod. zone		9. WELL NO. 36-S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* 41 miles south of Rock Springs, Wyoming		10. FIELD AND POOL, OR WILDCAT Clay Basin Gas Storage	
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) 167'		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SW SW 22-3N-24E	
16. NO. OF ACRES IN LEASE 1900.74		12. COUNTY OR PARISH Daggett	
17. NO. OF ACRES ASSIGNED TO THIS WELL -		13. STATE Utah	
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 4700' Unit #6		20. ROTARY OR CABLE TOOLS Rotary	
21. ELEVATIONS (Show whether DF, RT, GR, etc.) GR 6497'		22. APPROX. DATE WORK WILL START* After Unit #35-S	

## PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	9-5/8" new	36#, K-55	300'	180 sx, 3% CaCl
8-3/4"	7" new	23#, K-55	5957'	To be determined

We would like to drill the subject well to an estimated depth of 5957', anticipated formation tops are as follows: Mancos at the surface, Frontier at 5402', Mowry at 5602', Dakota at 5757', and Morrison at 5897'.

Mud will be adequate to contain formation fluids and in sufficient quantities to efficiently drill the well; blowout preventers will be checked daily and pressure tested after each string of casing is set; no cores, no DST's; no mud logging unit; 20 days drilling time; no abnormal temperatures, pressures, or H<sub>2</sub>S anticipated; probably run Laterlog & CDL logs.

APPROVED BY THE DIVISION OF  
OIL, GAS, AND MINING

DATE: 2-18-77

BY: C.B. Knight

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED R. E. Myers TITLE Manager, Drilling and Petroleum Engineering DATE Feb. 12, 1977

(This space for Federal or State office use)

PERMIT NO. B-009-30027 APPROVAL DATE \_\_\_\_\_APPROVED BY Cause 164-1 TITLE \_\_\_\_\_ DATE \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

Well Name Clay Basin Unit Well No. 36-SLocation SW SW 22-3N-24EDaggett County, Utah

<u>Wellhead Equipment</u>	<u>Size</u>	<u>Pressure Rating</u>	<u>Pressure Test</u>
Surface Casing Flange	10	3000	
Casing Spool			
Tubing Spool	10 x 6	3,000	6,000
Tubing Bonnet	10 x 4	3,000	6,000

<u>Blow Out Preventers</u> (Top to Bottom)	<u>Size</u>	<u>PSI Rating</u>	<u>PSI Test</u>	<u>Cap</u>	<u>Range</u>
	10	3,000	6,000		Blind
	10	3,000	6,000		4-1/2
<u>Gas Buster</u>	<u>Yes</u>	<u>X</u> No	<u>Dehydrator</u>	<u>Yes</u>	<u>X</u> No

Kill or Control Manifold

2"	3,000	6,000	No
<u>Size</u>	<u>Pressure Rating</u>	<u>Pressure Rating Test</u>	<u>Hydraulic Valves</u>

Auxiliary Equipment Kelly Cock

<u>X</u>	
Yes	No

Monitoring Equipment on Mud System

<u>X</u>	
Yes	No

Full Opening Drill Pipe  
Stabbing Valve on Floor

<u>X</u>	
Yes	No

Type of Drilling Fluid

<u>X</u>			
Water Base Mud	Air	Gas	Oil Base Mud

Anticipated Bottom Hole Pressure

500
PSI

STATE OF UTAH  
DIVISION OF OIL, GAS, AND MINING

*Gas Storage*

\*\* FILE NOTATIONS \*\*

Date: Feb. 16-  
Operator: Mountain Fuel Resources  
Well No. Clay Basin Unit 360  
Location: Sec. 22 T. 3N R. 24E, County: Daggett

File Prepared

☒

Entered on N.I.D.

☒

Card Indexed

☒

Completion Sheet

☒

Checked By:

Administrative Assistant: *[Signature]*

Remarks:

Petroleum Engineer: *[Signature]*

Remarks:

Director: *[Signature]*

Remarks:

Include Within Approval Letter:

Bond Required ☐

Survey Plat Required ☐

Order No. 164-1 ☒

Surface Casing Change ☐  
to \_\_\_\_\_

Rule C-3(c), Topographical exception/company owns or controls acreage  
within a 660' radius of proposed site ☐

O.K. Rule C-3 ☐

O.K. In Clay Basin Unit ☒

Other: \_\_\_\_\_

*[Signature]*  
Approved

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUBMIT IN TRIPLICATE\*  
(Other instructions on re-  
verse side)

Form approved.  
Budget Bureau No. 42-R1424.  
5. LEASE DESIGNATION AND SERIAL NO.

SL - 045051 b

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> Gas Storage		7. UNIT AGREEMENT NAME Clay Basin Gas	
2. NAME OF OPERATOR Mountain Fuel Resources, Inc.		8. FARM OR LEASE NAME Storage Agreement	
3. ADDRESS OF OPERATOR P. O. Box 1129, Rock Springs, Wyoming 82901		9. WELL NO. 36-S	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1001' FSL, 1067' FWL SW SW		10. FIELD AND POOL, OR WILDCAT Clay Basin Gas Storage	
14. PERMIT NO. API No.: 43-009-30027		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SW SW 22-3N-24E	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) GR 6487.5		12. COUNTY OR PARISH Daggett	
		13. STATE Utah	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐

FRACTURE TREAT ☐

SHOOT OR ACIDIZE ☐

REPAIR WELL ☐

(Other) ☐

PULL OR ALTER CASING ☐

MULTIPLE COMPLETE ☐

ABANDON\* ☐

CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐

FRACTURE TREATMENT ☐

SHOOTING OR ACIDIZING ☐

(Other) Move location ☒

REPAIRING WELL ☐

ALTERING CASING ☐

ABANDONMENT\* ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Location was moved per request of BLM, new location plats are attached.



18. I hereby certify that the foregoing is true and correct

SIGNED R. L. Myers

TITLE Manager, Drilling and Petroleum Engineering

DATE March 8, 1977

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_  
CONDITIONS OF APPROVAL, IF ANY:

TITLE \_\_\_\_\_

DATE \_\_\_\_\_

K

## INTEROFFICE COMMUNICATION

FROM T. M. Colson

Rock Springs, Wyoming  
CITY STATE

TO R. G. Myers

DATE May 2, 1977


SUBJECT Tentative Plan to Drill  
Unit Well No. 36-S  
Clay Basin Field

Attached for your information and files is a tentative plan to drill the above-captioned well. This plan was written in accordance with the Geologic Prognosis dated February 11, 1977.

TMC/gm

Attachment

cc: R. D. Cash  
E. R. Keller (3)  
G. A. Peppinger (3)  
A. J. Marushack  
A. K. Zuehlisdorff  
D. E. Dallas  
A. J. Maser (3)  
J. E. Adney  
E. J. Widic  
B. M. Steigleder  
E. A. Farmer  
D. L. Reese  
U.S.G.S.  
State *Me*  
Paul Zubatch  
P. E. Files (4)



From: Pat Brotherton

Rock Springs, Wyoming

To: T. M. Colson

May 2, 1977

Tentative Plan to Drill  
Unit Well No. 36-S  
Clay Basin Field

This well will be drilled to total depth by \_\_\_\_\_ Drilling Company. One work order has been originated for the drilling and completion of this well, namely 20046, Drill Unit Well No. 36-S, Clay Basin Field, located in the SW SW Sec. 22, T. 3 N., R. 24 E., Daggett County, Utah. An 8-3/4-inch hole will be drilled to a total depth of 5957 feet and 7-inch O.D. casing run. It is planned to complete the well as a gas storage well in the Dakota formation. Surface elevation is at 6487.5 feet.

1. Drill 12-1/4-inch hole to approximately 330 feet KBM.
2. Run and cement approximately 300 feet of 9-5/8-inch O.D., 36-pound, K-55, 8 round thread, LT&C casing. The casing will be cemented by Halliburton with 165 sacks of regular Type "G" cement with 3 percent calcium chloride, which represents theoretical requirements plus 100 percent excess cement for 9-5/8-inch O.D. casing in 12-1/4-inch hole with cement returned to surface. Plan on leaving a 10 foot cement plug in the bottom of the casing after displacement is completed. Floating equipment will consist of a Baker guide shoe. The top and bottom of all casing collars will be spot welded in the field and the guide shoe will be spot welded to the shoe joint in the Rock Springs Machine Shop. The bottom of the surface casing should be landed in such a manner that the top of the 10-inch 3000 psi casing flange will be at ground level. A cellar three feet deep will be required. Prior to cementing, circulate 50 barrels of mud. Capacity of the 9-5/8-inch O.D. casing is 24 barrels.
3. After a WOC time of 6 hours, remove the landing joint and wash off casing collar. Install a NSCo. Type "B" 10-inch 3000 psi regular duty casing flange tapped for 9-5/8-inch O.D. casing. Install a 2-inch extra heavy nipple, 6-inches long, and

a Demco (2000 psi WOG, 4000 psi test) ball valve on one side outlet of the casing flange and a 2-inch extra heavy bull plug in the opposite side. Install a 10-inch 3000 psi double gate hydraulically operated blowout preventer with blind rams in the bottom and 4-1/2-inch rams in the top and finish nipping up. After a WOC time of 12 hours, pressure test surface casing, all preventer rams, and Kelly-cock to 1000 psi for 15 minutes using rig pump and drilling mud. The burst pressure rating for 9-5/8-inch O.D., 36-pound, K-55, 8 round thread, LT&C casing is 3520 psi.

4. Drill 8-3/4-inch hole to the total depth of 5957 feet or to such depth as the Geological Department may recommend. The mud will consist of 2 percent potassium chloride water to 4500 feet. Mud up with the potassium Dexdrid Drispac system at this point to allow a 10 cc. water loss at 5650 feet. The 10 cc. water loss will be maintained to total depth at 5957 feet. If lost circulation is encountered, only acid soluble lost circulation material will be used. A mud cleaner will be used from surface to total depth to remove undesirable solids from the mud system and to keep the mud weight to a minimum. A Company Geologist will be on location to check cutting samples; 10 foot samples from 5300 feet to total depth. Anticipated tops are as follows:

	Approximate Depth (Feet KBM)
Mancos	Surface
Frontier	5,402
Mowry	5,602
Dakota	5,757
Morrison	5,897
Total Depth	5,957

Objective Reservoir: Dakota Formation

Other Possible

Producing Zones: Frontier Formation



5. Run a laterolog 7 with a split 4-decade logarithmic scale from surface casing to total depth. Run a compensated density/gamma ray/caliper from total depth at 5957 feet to 3957 feet. The 2000 feet logged represents the minimum footage for the log.
6. Assuming gas storage zones of good quality are present as indicated by log analysis, go into hole with 8-3/4-inch bit and drill pipe to total depth to condition mud prior to running production casing. Pull bit laying down drill pipe and drill collars.
7. Run 7-inch O.D. casing as outlined in Item No. I, General Information, through the deepest producing zone as indicated by log analysis. A Baker 7-inch O.D., 8 round thread, Type G circulating differential fillup collar and guide shoe will be run as floating equipment. Rig up Halliburton and cement casing with 50-50 Pozmix "A" cement. Bring cement top behind the 7-inch O.D. casing, 1000 feet above the uppermost producing zone as indicated by log analysis. Circulate 300 barrels of drilling mud prior to beginning cementing operations. Capacity of the 7-inch O.D. casing is approximately 234 barrels. Cement requirements will be based on actual hole size as determined by the caliper portion of the formation density log. Rotate casing while circulating, mixing, and displacing cement. Displace cement with water. Bump plug with 2500 psi and hold for 15 minutes to pressure test casing. Minimum burst pressure of the 7-inch O.D., 23-pound, K-55 casing is 4360 psi.
8. Immediately after cementing operations are completed, land the 7-inch O.D. casing with full weight of casing on slips in the 10-inch 3000 psi casing flange and record indicator weight. Install NSCo. Type DP-7, 10-inch 3000 psi by 6-inch

3000 psi tubing spool. Pressure test primary and secondary seals to 2500 psi for 5 minutes. Minimum collapse pressure for 7-inch O.D., 23-pound, K-55, 8 round thread, LT&C casing is 3280 psi. Install a steel plate on the 6-inch 3000 psi tubing spool flange.

9. Release drilling rig and move off location.
10. Move in and rig up a completion rig.
11. Install a 6-inch 5000 psi hydraulically operated double gate preventer with blind rams on bottom and 2-3/8-inch tubing rams on top.
12. After a WOC time of at least 50 hours, rig up Dresser Atlas and run bond log and perforating formation control log from plugged back depth to top of cement behind the 7-inch O.D. casing.
13. After a WOC time of at least 56 hours, pick up and run a 6-1/4-inch bit on 2-3/8-inch O.D., 4.7-pound, V-55, 8 round thread, EUE tubing to check plugged back depth. Rig up and displace drilling mud out of hole with drip oil. Pull and lay down 2-3/8-inch O.D. tubing.
14. Rig up Dresser Atlas perforating truck and perforate the Dakota storage sand with 2 HPF jumbo jet shots. The interval to be perforated will be chosen after the open hole logging has been reviewed and evaluated.
15. Rig up Dresser Atlas and run a Baker Model FB-1 packer (size 87-40) as follows:
  - Baker Model FB-1 packer (4.0-inch I.D. through packer).
  - 6 foot Baker millout extension (4.0-inch I.D.).
  - 10 foot Baker seal bore protector (4.0-inch I.D.) changeover.
  - 6 foot 3-1/2-inch O.D., 9.2-pound, J-55, 8 round EUE pup joint.
  - Baker Model "F" non-ported seating nipple (size 2.81).

6 foot 3-1/2-inch O.D., 9.2-pound, J-55, 8 round EUE pup joint.

Baker Model "R" non-ported no-go seating nipple (size 2.75).

Set packer so that the bottom of the assembly is 30 feet above the perforations.

Perforations will be chosen after the open-hole logging is completed.

16. Install 4-1/2-inch rams in preventer. Pick up a Baker locator seal assembly and a Baker Model "L" sliding sleeve and run tubing as follows:

1 NSCo. DP4-H-1 tubing hanger tapped 4-1/2-inch O.D., 8 round thread, LT&C, top and bottom.

4-1/2-inch O.D., 11.6-pound, J-55, 8 round thread, LT&C pup joints, as required to space out.

Approximately 187 joints 4-1/2-inch O.D., 11.6-pound, J-55, 8 round thread, LT&C tubing.

Baker Model "L" 4-1/2-inch O.D. sliding sleeve (size 3.812), in open position.

1 6 foot 4-1/2-inch O.D., 11.6-pound, J-55 pup joint.

Baker Model "G" locator seal assembly with 10 feet of seal extensions (I.D. 3.0-inches).

Land tubing in packer with 10,000 pounds compression. Space out and land in wellhead.

17. Install upper portion of wellhead.

18. Swab fluid out of wellbore. Run a short production test.

GENERAL INFORMATION


I. The following tubular goods have been assigned to the well.

<u>Description</u>	<u>Approximate Gross Measurement (feet)</u>	<u>Availability</u>
	<u>Surface Casing</u>	
9-5/8-inch O.D., 36-pound, K-55, 8 round thread, LT&C casing	330	Warehouse Stock
	<u>Production Casing</u>	
7-inch O.D., 23-pound, K-55, 8 round thread, LT&C casing (Bottom 400 feet will be rough coated)	6,000	Warehouse Stock
	<u>Production Tubing</u>	
4-1/2-inch O.D., 11.6-pound, J-55, 8 round thread, LT&C tubing	6,000	Warehouse Stock

II. All ram type preventers will have hand wheels installed and operative at the time the preventers are installed.

III. Well responsibility - D. L. Reese or G. G. Francis

This area should be leveled to stack drill pipe, set "Frog" tanks, testing separator, and other equipment.



#### GENERAL NOTES:

At sites where topsoil is present, same is to be removed and stored on the adjacent land for restoration of the site when required.

Mud pit and garbage pit are to be fenced, unlined.

For well location profiles see drawing number M-12406.

Area for well location 1.0 acres.

#### LEGEND





- ⊕ WELL
- ⊕ STONE CORNER
- ⊕ PIPE CORNER

#### DRILLING W.O.

#### ENGINEERING RECORD


SURVEYED BY	J.D. Gotfredson 1/31/77
REFERENCES	G.L.O. PLAT <input checked="" type="checkbox"/> U.S.G.S. QUAD. MAP <input type="checkbox"/>
LOCATION DATA	
FIELD	Clay Basin
LOCATION: SW 1/4, SW 1/4, Sec. 22, T.3 N., R. 24 E., Salt Lake Meridian, 1153' FWL, 950' FSL.	
Daggett County, Utah	
WELL ELEVATION: 6497' "As Graded" by electronic vertical angle elevations from M.F.S.Co. bench mark Δ 122	










PROFILE SECTION - PROPOSED GRADED LOCATION

Scale  
 HORIZ. 1" = 50'  
 VERT. 1" = 10'







KEY MAP  
Scale 1" = 100'

REVISIONS				 <b>MOUNTAIN FUEL RESOURCES, INC.</b>
NO.	DESCRIPTION	DATE	BY	
1	Rev. datum & Loc. Grade	5-11-77	A.H.W.	<b>PROFILES FOR CLAY BASIN UNIT WELL NO 36-S WELL LOCATION SITE</b>
				DRAWN: 2/23/77 C.R.W.    SCALE: AS NOTED
				CHECKED: G.L. SMF    DRWG. NO. M-12442
				APPROVED: RWH    2/2





REVISIONS				 <b>MOUNTAIN FUEL RESOURCES, INC.</b>
NO.	DESCRIPTION	DATE	BY	
				<b>TYPICAL PRODUCTION FACILITIES LAYOUT FOR CLAY BASIN UNIT WELL No 36-S</b>
DRAWN: 7/9/76 FJC		SCALE: NONE		DRWG. NO. <b>M-12205</b>
CHECKED:				
APPROVED:				

DEVELOPMENT PLAN FOR U.S.G.S. APPROVAL OF SURFACE USE  
MOUNTAIN FUEL SUPPLY COMPANY DRILLING WELLS

Well Name - Clay Basin Well No. 36-S

Field or Area - Clay Basin, Daggett County, Utah

1. Existing Roads -

- A) Proposed well site as staked - Refer to well location plat No. M-12405 for location of well access road and directional reference stakes.
- B) Route and distance from nearest town or locatable reference point to where well access route leaves main road - Refer to lateral map No. M-9030. From the Wyoming-Utah State Line to Rock Springs, Wyoming is 50 miles.
- C) Access road to location - Refer to lateral map No. M-9030 and well site map No. M-12405 for access road from Wyoming-Utah State Line to Clay Basin Unit Well No. 36-S.
- D) If exploratory well, all existing roads within a 3-mile radius of well site - Not an exploratory well
- E) If development well, all existing roads within a 1-mile radius - This will be a storage development well. Refer to later map No. M-9030 for existing roads.
- F) Plans for improvement and/or maintenance of existing roads - All existing roads will be maintained as needed by Mountain Fuel equipment.

2. Planned Access Road -

- A) Width - 16' wide from shoulder to shoulder.
- B) Maximum grade - The maximum grade on the road is 8 percent.
- C) Turnouts - No turnouts will be constructed.
- D) Drainage design - A drainage ditch on the uphill side of the road will be constructed. It will be a minimum of one foot below the surface of the road. No water diversion ditches are anticipated.
- E) Location and size of culverts and description of major cuts and fills -
  - 1) For culvert size and location see drawing No. M-12405
  - 2)
- F) Surfacing material - No surfacing material will be needed either on the road of location.
- G) Necessary gates, cattle guards or fence cuts - No cattle guards, gates, or fence cuts are anticipated.
- H) New or reconstructed roads - Refer to drawing No. M-12405 for location of new road. No existing road to be improved.

3. Location of Existing Wells -

- A) Water wells - None within a one mile radius.
- B) Abandoned wells - None within a one mile radius.
- C) Temporarily abandoned wells - None within a one mile radius.

- D) Disposal wells - None within a one mile radius.
  - E) Drilling wells - Refer to area map No. M-9030 for location of proposed wells.
  - F) Producing wells - Clay Basin Well Nos. 1, 7, 12, 13, 17, and 26 are productive gas wells.
  - G) Shut-in wells - None within a one mile radius.
  - H) Injection wells - Clay Basin Well Nos. 2, 4, and 11 are gas storage injection/withdrawal wells.
  - I) Monitoring or observation wells for other resources - None within a one mile radius.
4. Location of Existing And/Or Proposed Facilities - Refer to area map No. M-9030.
- A) 1) Tank batteries - None within a one mile radius.
  - 2) Production facilities - Each productive gas well has its own production facilities. Also, a compressor plant is located near Unit Well No. 3. Also, a compressor plant for injection is being built near Unit Well No. 3.
  - 3) Oil gathering lines -  
No oil gathering lines are located in the Clay Basin area.
  - 4) Gas gathering lines - Refer to drawing No. M-9030. Several gas laterals exist within a one mile radius.
  - 5) Injection lines - Several injection/withdrawal lines are located within a one mile radius. Refer to area map No. M-9030.
  - 6) Disposal lines -  
None within a one mile radius.
  - B) 1) Proposed location and attendant lines by flagging if off the well pad -  
The well will be used as a gas storage well. A 6-inch buried line will be installed from the well to the central dehydration facilities as shown on drawing No. M-9030.
  - 2) Dimensions of facilities - Refer to drawing No. M-12205.
  - 3) Construction methods and materials - No construction materials are anticipated. The dirt work will be done with a back hoe, i.e., ditches, dehydration base, tank base, etc.
  - 4) Protective measures and devices to protect livestock and wildlife -  
The sump pit will be fenced as shown on drawing No. M-12205.
  - C) Plans for rehabilitation of disturbed area no longer needed for operations after construction is completed - After construction is complete, areas of non-use will be restored and seeded.
5. Location and Type of Water Supply -
- A) Location of water - The water withdrawal point on Red Creek is located in the SW 1/4 of Section 22, T.12N., R.105W., of the 6th P.M., Sweetwater County, Wyoming.
  - B) Method of transporting water - Water will be hauled by tank truck from Red Creek to Unit Well No. 36-S. The well access road, as shown on drawing No. M-9030, will be used as the water haul road.

C) Water well to be drilled on lease - No water well will be drilled.

6. Source of Construction Material -

A) Information - No construction material will be used.

B) Identify if from Federal or Indian land -

C) Where materials are to be obtained and used -

D) Access roads crossing Federal or Indian lands -

7. Method for Handling Waste Disposal -

A-D) Cuttings, drilling fluids, produced fluids, and sewage will be placed in the mud pit.

E) Garbage and other waste material will be placed in the burn pit.

F) After drilling operations have been completed, the location will be cleared of all litter, and the trash will be burned in the burn pit. The burn pit will be covered over. The mud pit liquids will be pumped out and dumped on the existing roads. The mud pit will be covered over.

8. Ancillary Facilities - There now is a camp located in the NE 1/4 of Section 21, T.3N., R.24E. with housing and general camp facilities. A landing strip is located on the north line of Section 21. Water is piped to the camp from a spring to the west.

9. Well Site Layout -

See drawing Nos. M-12405 and M-12406.

10. Plans for Restoration of Surface -

A) After drilling operations, the well site will be cleared and cleaned and the burn pit filled in. Should the well be a dry hole, the surface will be restored to the extent that it will blend in with the landscape. The reserve pit liquids will be pumped out and dumped on the existing roads.

B) Revegetation and rehabilitation of the location and access road will be done to comply with Bureau of Land Management recommendations.

C) Prior to rig release, pits will be fenced and so maintained until clean up.

D) If oil is in the mud pit, overhead flagging will be installed to keep birds out.

E) Clean up will begin within two months after drilling operations have been completed and the land will be restored at this time.

11. Other Information -

A) The location lies at the base of a hill that slopes down to the west at  $\pm 20\%$ . The soil is clay. The vegetation is native grass and sagebrush. The access road bears west more or less and junctions with an existing field road.

B) The surface belongs to the U.S. Government.

C) Water can be located in Red Creek. The Clay Basin camp is occupied by Mountain Fuel personnel. No historical, archaeological, or cultural sites are in the area to my knowledge.

12. Lessee's or Operator's Representative -

D. E. Dallas, Drilling Superintendent, P. O. Box 1129, Rock Springs, Wyoming 82901, telephone 307-362-5611.

13. Certification -

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed herein will be performed by Mountain Fuel Supply Company and its contractors and sub-contractors in conformity with this plan and the terms and conditions under which it is approved.

Date \_\_\_\_\_

Name Dale D. Heston  
Title Drilling Superintendent

cdk

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEYP1  
SUBMIT IN TRIPPLICATE\*  
(Other instructions on re-  
verse side)Form approved.  
Budget Bureau No. 42-R1424.

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> Gas Storage		5. LEASE DESIGNATION AND SERIAL NO. SLC 045051 b
2. NAME OF OPERATOR Mountain Fuel Resources, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME -
3. ADDRESS OF OPERATOR P. O. Box 1129, Rock Springs, Wyoming 82901		7. UNIT AGREEMENT NAME Clay Basin Gas Storage Agreement
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface  1001' FSL, 1067' FWL SW SW		8. FARM OR LEASE NAME Unit Well
14. PERMIT NO. API No.: 43-009-30027		9. WELL NO. 36-S
15. ELEVATIONS (Show whether DF, RT, GR, etc.) KB 6455.10' GR 6437.50'		10. FIELD AND POOL, OR WILDCAT Clay Basin Gas Storage
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SW SW 22-3N-24E
		12. COUNTY OR PARISH Daggett
		13. STATE Utah

## 16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

## NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐PULL OR ALTER CASING ☐FRACTURE TREAT ☐MULTIPLE COMPLETE ☐SHOOT OR ACIDIZE ☐ABANDON\* ☐REPAIR WELL ☐CHANGE PLANS ☐(Other) ☐

## SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐REPAIRING WELL ☐FRACTURE TREATMENT ☐ALTERING CASING ☐SHOOTING OR ACIDIZING ☐ABANDONMENT\* ☐(Other) Supplementary history ☒

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

## 17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

TD 5885', spudded April 30, 1977, landed 9-5/8"OD, 32.3#, H-40, casing at 263.81' KBM and set with 180 sacks regular class G cement treated with 5% calcium chloride, cement in place April 25, 1977, landed 7"OD, 23#, K-55, casing at 5881.02' KBM and set with 450 sacks 50-50 Pozmix cement treated with 2% gel, cement in place May 7, 1977, rig released May 7, 1977, waiting on completion tools.

## 18. I hereby certify that the foregoing is true and correct

SIGNED G. D. Myers

TITLE

Manager, Drilling and  
Petroleum Engineering

DATE May 14, 1977

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_

TITLE \_\_\_\_\_

DATE \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions on Reverse Side

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUBMIT IN TRIPLICATE\*  
(Other instructions on re-  
verse side)

Form approved.  
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

SLC 045051 b

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT" for such proposals.)

1. OIL WELL ☐ GAS WELL ☐ OTHER ☐ Gas Storage

2. NAME OF OPERATOR

Mountain Fuel Resources, Inc.

3. ADDRESS OF OPERATOR

P. O. Box 1129, Rock Springs, Wyoming 82901

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.\*  
See also space 17 below.)  
At surface

1001' FSL, 1067' FWL SW SW

7. UNIT AGREEMENT NAME

Clay Basin Gas  
Storage Agreement

8. FARM OR LEASE NAME

Unit Well

9. WELL NO.

36-S

10. FIELD AND POOL, OR WILDCAT

Clay Basin Gas Storage

11. SEC., T., R., M., OR BLK. AND  
SURVEY OR AREA

SW SW 22-3N-24E

14. PERMIT NO.

API No.: 43-009-30027

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

KB 6455.10'

GR 6437.50'

12. COUNTY OR PARISH

Daggett

13. STATE

Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

☐  
☐  
☐  
☐

PULL OR ALTER CASING

☐  
☐  
☐  
☐

FRACTURE TREAT

MULTIPLE COMPLETE

SHOOT OR ACIDIZE

ABANDON\*

REPAIR WELL

CHANGE PLANS

(Other)

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

☐  
☐  
☐  
☐

REPAIRING WELL

☐  
☐  
☐  
☒

FRACTURE TREATMENT

ALTERING CASING

SHOOTING OR ACIDIZING

ABANDONMENT\*

(Other)

Supplementary history

(NOTE: Report results of multiple completion on Well  
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

TD 5885', PBD 5830', rigged up completion tools on 6-15-77, perforated Dakota from 5711' to 5791' with 2 jumbo jet shots per foot, set packer at 5611', landed 4-1/2" tubing at 5621.43', swabbed, well began flowing, flowed 2 hours, shut well in, rig released June 17, 1977.

Final report.

18. I hereby certify that the foregoing is true and correct

SIGNED

*W. Dallas*

TITLE Drilling Superintendent

DATE June 21, 1977

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

Well Name Clay Basin Unit Well No. 36-SLocation SW SW 22-3N-24EDaggett County, Utah

<u>Wellhead Equipment</u>	<u>Size</u>	<u>Pressure Rating</u>	<u>Pressure Test</u>
Surface Casing Flange	<u>10</u>	<u>3000</u>	
Casing Spool			
Tubing Spool	<u>10 x 6</u>	<u>3,000</u>	<u>6,000</u>
Tubing Bonnet	<u>10 x 4</u>	<u>3,000</u>	<u>6,000</u>

<u>Blow Out Preventers</u> (Top to Bottom)	<u>Size</u>	<u>PSI Rating</u>	<u>PSI Test</u>	<u>Bag</u>	<u>Range</u>
	<u>10</u>	<u>3,000</u>	<u>6,000</u>		<u>Blind</u>
	<u>10</u>	<u>3,000</u>	<u>6,000</u>		<u>4-1/2"</u>

<u>Gas Buster</u>	<u>Yes</u>	<u>X</u> <u>No</u>	<u>Degasser</u>	<u>Yes</u>	<u>X</u> <u>No</u>

<u>Kill or Control Manifold</u>	<u>2"</u> <u>Size</u>	<u>3,000</u> <u>Pressure Rating</u>	<u>6,000</u> <u>Pressure Rating Test</u>	<u>No</u> <u>Hydraulic Valves</u>

<u>Auxiliary Equipment</u>	<u>Kelly Cock</u>	<u>X</u> <u>Yes</u>	<u>No</u>

<u>Monitoring Equipment on Mud System</u>	<u>Yes</u>	<u>X</u> <u>No</u>

<u>Full Opening Drill Pipe Stabbing Valve on Floor</u>	<u>X</u> <u>Yes</u>	<u>No</u>

<u>Type of Drilling Fluid</u>	<u>X</u> <u>Water Base Mud</u>	<u>Air</u>	<u>Gas</u>	<u>Oil Base Mud</u>

<u>Anticipated Bottom Hole Pressure</u>	<u>500</u> <u>PSI</u>



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE\*

(See other in-  
structions on  
reverse side)Form approved.  
Budget Bureau No. 42-R355.5.

13

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> Other <u>Gas Storage</u>		5. LEASE DESIGNATION AND SERIAL NO. SLC - 045051 b	
b. TYPE OF COMPLETION: NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> Other <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME -	
2. NAME OF OPERATOR Mountain Fuel Resources, Inc.		7. UNIT AGREEMENT NAME Clay Basin Gas Storage Agreement	
3. ADDRESS OF OPERATOR P. O. Box 1129, Rock Springs, Wyoming 82901		8. FARM OR LEASE NAME Unit Well	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)* At surface 1001' FSL, 1067' FWL SW SW At top prod. interval reported below At total depth		9. WELL NO. 36-S	
14. PERMIT NO. API No.: 43-009-30027		12. COUNTY OR PARISH Daggett	
15. DATE SPUDDED 4-30-77		13. STATE Utah	
16. DATE T.D. REACHED 5-5-77		18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* KB 6455.10' GR 6437.50'	
17. DATE COMPL. (Ready to prod.) 6-17-77		19. ELEV. CASINGHEAD -	
20. TOTAL DEPTH, MD & TVD 5885'		21. PLUG, BACK T.D., MD & TVD 5830'	
22. IF MULTIPLE COMPL., HOW MANY*		23. INTERVALS DRILLED BY 0-5885'	
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* 5711 - 5791' Dakota		25. WAS DIRECTIONAL SURVEY MADE No	
26. TYPE ELECTRIC AND OTHER LOGS RUN Dual Laterolog, Compensated Densilog		27. WAS WELL CORED No	
28. CASING RECORD (Report all strings set in well)			
CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE
9-5/8"	32.3	263.81'	12-1/4"
7"	23	5,881.02'	8-3/4"
29. LINER RECORD			
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*
30. TUBING RECORD			
SIZE	DEPTH SET (MD)	PACKER SET (MD)	
4-1/2"	5621.43'	5611'	
31. PERFORATION RECORD (Interval, size and number) 5711-5791', jumbo jet, 2 holes per foot			
32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.			
DEPTH INTERVAL (MD)		AMOUNT AND KIND OF MATERIAL USED	
33.* PRODUCTION			
DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) Flowing - GAS STORAGE	
DATE OF TEST		WELL STATUS (Producing or shut-in) Shut in	
HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	GAS—MCF.
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Vented while testing.		TEST WITNESSED BY	
35. LIST OF ATTACHMENTS Logs as above, Well Completion to be sent at a later date.			
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records			
SIGNED <u>Thomas A. Smith</u>		TITLE <u>Petroleum Engineering</u>	
DATE <u>June 21, 1977</u>			

\*(See Instructions and Spaces for Additional Data on Reverse Side)

# INSTRUCTIONS

**General:** This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions. If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

**Item 4:** If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

**Item 18:** Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments.

**Items 22 and 24:** If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

**Item 29: "Sacks Cement":** Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

**Item 33:** Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES: SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF: CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES				38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
				Log tops:		
				Mancos	0'	
				Frontier	5356'	
				Mowry	5550'	
				Dakota	5710'	

COMPLETION REPORT

Well: Clay Basin Unit No. 36-S Date: October 3, 1977

Area: Clay Basin Lease No: SLC - 045051 b

☐ New Field Wildcat ☒ Development Well ☐ Shallower Pool Test  
☐ New Pool Wildcat ☐ Gas Storage ☐ Deeper Pool Test  
☐ Extension

Location: 1001 feet from South line, 1067 feet from West line  
SW  $\frac{1}{4}$  SW  $\frac{1}{4}$

Section 22, Township 3 North, Range 24 East

County: Daggett State: Utah

Operator: Mountain Fuel Resources, Inc.

Elevation: KB 64-5.10 Gr 6437.50 Total Depth: Driller 5885 Log 5879

Drilling Commenced: April 30, 1977 Drilling Completed: May 5, 1977

Rig Released: May 7, 1977 Well Completed: June 17, 1977

Sample Tops: (unadjusted)

Log Tops:

Mancos	Surface
Frontier	5356
Mowry	5550
Dakota	5710
Morrison	5849

Sample Cuttings: None

Status: Gas storage injection/withdrawal well

Producing Formation: Dakota

Perforations: 5711-5791, jumbo jet, 2 holes per foot

Stimulation: None

Production: None reported

Plug Back Depth: 5830

Plugs: None

Hole Size: 12-1/4" to 366; 8-3/4" to 5885

Casing/Tubing: 9-5/8" to 263.81, 7" to 5881.02; 4-1/2" to 5621.43, with packer  
set at 5611

Logging - Mud: None

Mechanical: Dual Laterolog (265-5877), Compensated Densilog (3879-5878)

Contractor: Signal Drilling Company

Completion Report Prepared by: M. L. Tomac

Remarks: API No. 4300930027



COMPLETION REPORT (cont.)

Page 2

Well: Unit No. 36-S

Area: Clay Basin

Cored Intervals (recovery): None

Tabulation of Drill Stem Tests: None

<u>No.</u>	<u>Interval</u>	<u>IHP</u>	<u>IFP (min.)</u>	<u>ISIP (min.)</u>	<u>FFP (min.)</u>	<u>FSIP (min.)</u>	<u>FHP</u>	<u>Samples Caught</u>	<u>Remarks</u>
------------	-----------------	------------	-------------------	--------------------	-------------------	--------------------	------------	-----------------------	----------------

15 June 00

N

○ will head


meter  
man



Access  
road

12-381 50 SHEETS 5 SQUARE  
12-382 100 SHEETS 5 SQUARE  
12-389 200 SHEETS 5 SQUARE





## QUESTAR PIPELINE COMPANY

79 SOUTH STATE STREET • P. O. BOX 11450 • SALT LAKE CITY, UTAH 84147 • PHONE (801) 530-2400  
June 23, 1988

CERTIFIED MAIL  
RETURNED RECEIPT REQUESTED  
#P 879 571 459

Bureau of Land Management  
Utah State Office  
CFS Financial Center  
324 S. State Street  
Salt Lake City, UT 84111-2303

Re: Name Change  
Mountain Fuel Resources, Inc.  
to Questar Pipeline Company

Gentlemen:


Enclosed for your files and information is a certified copy of the Articles of Amendment to the Articles of Incorporation of Mountain Fuel Resources, Inc. dated March 7, 1988, indicating that Mountain Fuel Resources, Inc. changed its name to Questar Pipeline Company.

Questar Pipeline Company holds interests in the following Federal Oil and Gas Leases in Utah:

*NO wells on Gas hold.*  
*with CA*  
*CA well - RT 100% Mt. Fuel Resources - U-9712-A - Questar 100%*  
*U-11246 - Assignment pending to "Questar Energy Co."*  
SLC-045051(A) > OR'S  
SLC-045051(B) > OR'S  
SLC-045053(A) > OR'S  
SLC-045053(B) > OR'S  
SLC-062508 - OR'S  
SLC-070555 - OR'S  
SLC-070555(A) - OR'S  
Agreement No. 14-08-0001-16009  
(Clay Basin Gas Storage Agreement)  
*Vernal*

Please note and adjust your records in accordance with the above and furnish verification of your receipt of this notice to the undersigned.

Sincerely,

  
J. B. Neese  
Senior Landman

JBN/sdg

Enclosure

List of Leases

Overriding Royalties

U-09712-A  
U-011246

Operating Rights

SL-045051-A & B  
SL-045053-A & B  
SL-062508  
SL-0700555  
SL-070555-A  
SL-045049-A & B

Clay Basin Gas Storage Agreement  
Agreement No. 14-08-0001-16009

3100  
U-09712-A  
et al  
(U-942)

C. Seare  
3/9/89

### DECISION

Questar Pipeline Company : Oil and Gas Leases  
P.O. Box 11450 : U-09712-A et al  
Salt Lake City, Utah 84147 :

#### Corporate Name Change Recognized

Acceptable evidence has been received establishing that Mountain Fuel Resources, Inc. has changed their name to Questar Pipeline Company. Accordingly, the surviving company, Questar Pipeline Company, is recognized as holding all interests in Federal oil and gas leases which were held by Mountain Fuel Resources, Inc. We are changing our records with respect to the attached listing of oil and gas leases. If there are any other leases that will be affected, please contact this office.

/s/ M. Willis

ACTING Chief, Minerals  
Adjudication Section

Enclosure  
List of Leases

cc: All District Offices, Utah  
MMS, AFS  
MMS, BRASS  
920, Teresa Thompson  
Clay Basin Unit File

CSeare:s1 3/9/89:1642f

RECEIVED

JAN 28 2004

DIV. OF OIL, GAS & MINING



## OPERATOR CHANGE WORKSHEET

## ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

**X** Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

**3/7/1988**

FROM: (Old Operator):	TO: (New Operator):
N1070-Wexpro Company PO Box 45360 Salt Lake City, UT 84145-0360 Phone: 1-(801) 534-5267	N7560-Questar Pipeline Company PO Box 11450 Salt Lake City, UT 84147 Phone: 1-(801) 530-2019

CA No.

Unit:

## WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
CLAY BASIN UNIT 39-S	21	030N	240E	4300930030	1025	Federal	GS	A
CLAY BASIN UNIT 48-S	21	030N	240E	4300930044	1025	Federal	GS	A
CLAY BASIN UNIT 50-S	21	030N	240E	4300930046	1025	Federal	GS	A
CLAY BASIN UNIT 51-S	21	030N	240E	4300930047	1025	Federal	GS	A
CLAY BASIN UNIT 58-S	21	030N	240E	4300930054	1025	Federal	GS	A
CLAY BASIN UNIT 60-S	21	030N	240E	4300930056	1025	Federal	GS	A
CLAY BASIN U 11 (RD MURPHY 6-W)	22	030N	240E	4300915635	1025	Federal	GS	A
CLAY BASIN 28-S	22	030N	240E	4300930021	1025	Federal	GS	A
CLAY BASIN UNIT 32-S	22	030N	240E	4300930023	1025	Federal	GS	A
CLAY BASIN UNIT 36-S	22	030N	240E	4300930027	1025	Federal	GS	A
CLAY BASIN UNIT 54-S	22	030N	240E	4300930050	1025	Federal	GS	A
CLAY BASIN U 6 (RD MURPHY 3)	23	030N	240E	4300915630	1025	Federal	GS	A
CLAY BASIN U 10 (1 CL SPARKS)	23	030N	240E	4300915634	1025	Federal	GS	A
CLAY BASIN UNIT 29-S	23	030N	240E	4300930020	1025	Federal	GS	A
CLAY BASIN UNIT 31-S	23	030N	240E	4300930022	1025	Federal	GS	A
CLAY BASIN UNIT 44-S	23	030N	240E	4300930040	1025	Federal	GS	A
CLAY BASIN UNIT 45-S	23	030N	240E	4300930041	1025	Federal	GS	A
CLAY BASIN UNIT 57-S	24	030N	240E	4300930053	1025	Federal	GS	A
CLAY BASIN UNIT 41-S	26	030N	240E	4300930032	1025	Federal	GS	A
CLAY BASIN UNIT 42-S	26	030N	240E	4300930033	1025	Federal	GS	A
CLAY BASIN UNIT 43-S	26	030N	240E	4300930039	1025	Federal	GS	A

## OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 1/13/2004
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 1/13/2004
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 1/14/2004
4. Is the new operator registered in the State of Utah: YES Business Number: 649172-0142
5. If **NO**, the operator was contacted on: \_\_\_\_\_

6. (R649-9-2)Waste Management Plan has been received on:

IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: 3/9/1989

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on:

n/a

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on:

n/a

10. **Underground Injection Control ("UIC"** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

**DATA ENTRY:**

1. Changes entered in the Oil and Gas Database on:

1/29/2004

2. Changes have been entered on the Monthly Operator Change Spread Sheet on:

1/29/2004

3. Bond information entered in RBDMS on:

1/29/2004

4. Fee wells attached to bond in RBDMS on:

1/29/2004

5. Injection Projects to new operator in RBDMS on:

n/a

**STATE WELL(S) BOND VERIFICATION:**

1. State well(s) covered by Bond Number:

965003032

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number:

965002976

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number:

n/a

**FEE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number

965003033

2. The **FORMER** operator has requested a release of liability from their bond on:

N/A

The Division sent response by letter on:

N/A

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 1/29/2004

**COMMENTS:**

# NEW ENTITY NUMBERS ASSIGNED FEBRUARY 2004

ACCT	OPERATOR NAME	API NUM.	Sec	Twnsnp	Rng	WELL NAME	ENTITY	EFF DATE	REASON
N7560	Questar Pipeline Co	4300915629	20	030N	240E	Clay Basin Unit 5	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300915627	16	030N	240E	Clay Basin Unit 3	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930018	16	030N	240E	Clay Basin Unit 27-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930048	16	030N	240E	Clay Basin Unit 52-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930049	16	030N	240E	Clay Basin Unit 53-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930055	16	030N	240E	Clay Basin Unit 59-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930026	17	030N	240E	Clay Basin Unit 35-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930031	20	030N	240E	Clay Basin Unit 40-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930045	20	030N	240E	Clay Basin Unit 49-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300915626	21	030N	240E	Clay Basin Unit 2	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930015	21	030N	240E	Clay Basin 24-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930016	21	030N	240E	Clay Basin Unit 25-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930017	21	030N	240E	Clay Basin Unit 26-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930019	21	030N	240E	Clay Basin 30-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930024	21	030N	240E	Clay Basin Unit 33-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930030	21	030N	240E	Clay Basin Unit 39-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930044	21	030N	240E	Clay Basin Unit 48-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930046	21	030N	240E	Clay Basin Unit 50-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930047	21	030N	240E	Clay Basin Unit 51-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930054	21	030N	240E	Clay Basin Unit 58-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930056	21	030N	240E	Clay Basin Unit 60-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300915635	22	030N	240E	Clay Basin U 11 (RD Murphy)	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930021	22	030N	240E	Clay Basin 28-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930023	22	030N	240E	Clay Basin Unit 32-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage
N7560	Questar Pipeline Co	4300930027	22	030N	240E	Clay Basin Unit 36-S	1025 to 14040	2/10/2004	Clay Basin Gas Storage

Note to file: These entity numbers  
were changed to compliment the  
operator correction from 3/7/98